

Job Name: 25-3193 - KYTC Kenton Co Call 328 (251320) Job Location: Independence, KY Contractor: Eaton Asphalt					Plant: 100		Tech: Jared - A				
					7/1/2026 12:30:45 PM		PC: J. Jarvis				
Structure ID: 193											
P1 MH048BAVF			MH BASE Custom Ht								
P3) 24" - CASTING HEIGHT - 7" P2) 48" - CON CONE w/24" HOLE - 36" P1) 48" - MH BASE Custom Ht - 25" 1) 48" - MH INVERT CHANNEL - FULL HEIGHT 1) CASTING - HOE MC-375 F/C Sanitary 1) 48" - Conseal CS-102 1.00" (Double) 2) PSX - 16L NYLO 4) MH Step ML-10-TDS-NCR - 10"						0 lb 2252 lb 2905 lb 1440 lb 271 lb 0 lb 16 lb 0 lb ----- Structure Total: 6885 lb		Structure Notes: 1. HOE MC-375-WT F/C SANITARY PROVIDED BY ICAST. 2. PER ASTM C478 SPECIFICATIONS. 3. CONCRETE = 4,000 PSI AT 28 DAYS. 4. REINFORCING PER ASTM A615 (GRADE 60). - CONE (As .12) - RISER/WALLS (As .12) - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.			
Rim: 782.2' Rim to Invert: 5.5' Slack: 0" Sump: 2" Step Position: 0°											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset	
Invert 1	776.7'	0°	0"	12" PVC SDR35	12.5"	PSX 16L NYLO	16"	16.312"	0"	0"	
Invert 2	776.8'	150°	75.922"	12" PVC SDR35	12.5"	PSX 16L NYLO	16"	16.312"	1.2"	0"	
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											

RIGHT-SIDE UP VIEW (int. dimensions)

UPSIDE-DOWN VIEW (int. dimensions)

INSIDE WALL DIMENSIONS

Coating (Int): Coating (Ext):	Seam Up: Tongue Seam Dn: n/a	Wall Thickness: 5" Floor Height: 6"	Height (Int): 25" Height (Ext): 31"	Weight (Net): 2905 lb Volume (Net): 0.74cu.yd
----------------------------------	---------------------------------	--	--	--