

Job Name: 26-1000P2 Clark Distributing New HQ - Site Structures Job Location: Bowling Green, KY Contractor: Scotty's Contracting & Stone, LLC							Plant: Beaver Dam 8/11/2026 9:19:10 AM		Tech: S. Felletter PC: M. Sullivan			
Structure ID: DBI-19												
P1		BX2436-08BVF			BOX BASE 8inW, 8inF, Variable Ht F/n							
P3) 24" x 30" - CASTING HEIGHT - 3.50" P2) 24" x 36" - BX FLAT LID 8inW w/24"x30" HOLE F/F - 6" P1) 24" x 36" - BOX BASE 8inW, 8inF, Variable Ht F/n - 33" 1) CASTING - HOE KY-460-11 F/G (DBI 11) 1) 24" x 36" - Conseal CS-102 1.00" 1) 24" x 30" - Conseal CS-102 1.00" 1) DOGHOUSE INVRTD - 38"x35"							0 lb 685 lb 4155 lb 421 lb 0 lb 0 lb 0 lb ----- Structure Total: 5261 lb		Structure Notes: 1. PER ASTM C913 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. CASTING BY ICAST (HOE KY-460-11 F/G). REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W. - WALLS (As .12) #5 BARS AT 12" C.C.E.W. - FLOOR (As .12) #5 BARS AT 12" C.C.E.W.			
Rim: 589.33'		Rim to Invert: 3.61'		Slack: 0.82"		Sump: 0"	Step Position: 90°					
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector		Hole	Horz Size	Up ()	Offset	
Invert 1	585.72'	90°	26"	30" HDPE	35.1"	DOGHOUSE INVRTD 38"x35"		38" x 35"	37"	-2.55"	0"	
Invert 2												
Invert 3												
Invert 4												
Invert 5												
Invert 6												
Invert 7												
Invert 8												
RIGHT-SIDE UP VIEW (int. dimensions)						UPSIDE-DOWN VIEW (int. dimenions)						
(P3) (P2) (P1) <<						Invert: 1 Degree: 90° Horz: 18" Hole: 38" x 35" Up(): -2.55" Invert: 1 Degree: 90° Horz: 18" Hole: 38" x 35" Up(): -2.55"						
INSIDE WALL DIMENSIONS												
Coating (Int): Coating (Ext):				Seam Up: Flat Seam Dn: n/a		Wall Thickness: 8" Floor Height: 8"		Height (Int): 33" Height (Ext): 41"		Weight (Net): 4155 lb Volume (Net): 1.06cu.yd		