



1. MANUFACTURED PER ASTM C-913 LATEST REVISION)
2. CONCRETE: 5,000 PSI AT 28 DAYS
3. REINFORCEMENT: #4 BAR @ 6" C.C. E.W. (GRADE 60) - 2" MIN. REBAR CLEARANCE (TYP)
4. WEIGHT: 3,200 LBS
5. 3/4" HDPE WEIR, 3/4" HDPE BAFFLE, & STAINLESS STEEL HOODED SCREEN SUPPLIED BY OTHERS
6. SPECIAL PRE-ASSEMBLY OF INTERNALS BY ICAST



THIS DRAWING IS THE PROPERTY OF INFRASTRUCTURE PRECAST, INC. ANY USE OR DUPLICATION OF THIS DRAWING WITHOUT PRIOR AUTHORIZATION IS STRICTLY PROHIBITED.

Job Number:

26-2700

Job Name:

2787 Convergent Pretx Curb Inlet

Structure:

QL2

Note:

Special Pre-Assembly of Internals To
Be Performed By iCast