



Job Name: 24-3406F Southeast Municipal Complex Job Location: Franklin, TN Contractor: Hayes Pipe Supply					Plant: Beaver Dam 7/6/2026 4:09:33 PM		Tech: J. Horsley PC: E. Bradley				
Structure ID: CB-054B											
P1		MH060RSVF		MH RISER Custom Ht T/G							
P1) 60" - MH RISER Custom Ht T/G - 16" 1) 60" - Conseal CS-102 1.00"						1670 lb 0 lb ----- Structure Total: 1670 lb		<u>Structure Notes:</u> 1. PER ASTM C-478 SPECIFICATIONS 2. CONCRETE: 4,000 PSI AT 28 DAYS 3. REINFORCEMENT: PER ASTM A615 4. STEPS AT 0 DEGREES 5. NO OPENINGS - BLANK BASE			
Rim: 1.333'		Rim to Invert: 0'		Slack: 0"		Sump: 0"		Step Position: 0°			
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset	
Invert 1											
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions)											
											
INSIDE WALL DIMENSIONS											
(P1)											
Coating (Int): Coating (Ext):				Seam Up: Tongue Seam Dn: Groove		Wall Thickness: 6" Floor Height: 0"		Height (Int): 16" Height (Ext): 16"		Weight (Net): 1670 lb Volume (Net): 0.43cu.yd	