

Job Name: 24-4208 - KYTC Christian Co. Call 100 (ID 241018) Job Location: Hopkinsville, KY Contractor: Scotty's Contracting & Stone, LLC				Plant: Beaver Dam 8/3/2026 4:28:43 PM		Tech: J. Horsley PC: C. Goff					
Structure ID: 310 (452+55 RT) P2 BX3232-08R24 BOX RISER 8inW F/G											
P4) CASTING (cast in) - 0 P3) 32" x 32" - BX FLAT LID 8inW SPEC. (KY JB-B1) F/F - 8" P2) 32" x 32" - BOX RISER 8inW F/G - 24" P1) 32" x 32" - BOX BASE 8inW, 8inF, Variable Ht T/n - 50" 1) CASTING - HOE KY-206 F/C (KY TY1) 2) 32" x 32" - SGL 1"x14.5' Butyl 2) Hole - 30 1) Hole - 20						0 lb 1243 lb 2578 lb 5757 lb 206 lb 0 lb 0 lb 0 lb ----- Structure Total: 9784 lb		Structure Notes: . **KYTC STATE PROJECT** 1. KYTC JUNCTION BOX B1 / PER ASTM C913 SPEC'S. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. TOP SLAB w KYTC TYPE 1 F/C CAST FLUSH. . REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As. 62) #5 BARS AT 6" C.C.E.W. - WALLS (As .31) #5 BARS AT 12" C.C.E.W. - FLOOR (As .31) #5 BARS AT 12: C.C.E.W.			
Rim: 527.3' Rim to Invert: 6.86' Slack: 0.32" Sump: 0" Step Position:											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (┘)	Offset	
Invert 1											
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions) (P4) (P3) (P2) << (P1) 32" 32" + 0°-											