

**Job Name: 25-1011 Maxie Plaza**  
**Job Location: Elizabethtown, KY 42740**  
**Contractor: Kauffeld Brothers Construction**

PC: C. Goff  
 TECH: J. Horsley  
 Plant: Beaver Dam



Structure ID: A (DBI 24x24)  
 Spec: Storm  
 Type: BX 8inW, 8inF  
 Size: 24" x 24"

Rim: 736.35'  
 Invert: 733.35'  
 Rim to Invert: 3'

Sump: 0"  
 Floor (Top): 733.35'  
 Floor Height: 8"

Overall Height: 3.667'  
 Slack: 0"


**Structure Notes:**

1. PER ASTM C913 SPECIFICATIONS.
2. CONCRETE = 4,000 PSI AT 28 DAYS.
3. NO INVERT CHANNEL.
4. CASTIG BY ICAST (HOE 342 F/G).


REINFORCING PER ASTM A615 (GRADE 60).  
 - WALLS (As .12) #5 BARS AT 12" C.C.E.W.  
 - FLOOR (As .12) #5 BARS AT 12" C.C.E.W.

**STRUCTURE SUMMARY:**


P2) 24" x 24" - CASTING HEIGHT - 6"	0 lb
P1) 24" x 24" - BOX BASE 8inW, 8inF F/n - 30"	3481 lb
1) CASTING - HOE 342 F/G	250 lb
1) 24" x 24" - Conseal CS-102 1.00"	0 lb
1) Hole - 18	0 lb
	-----
<b>Structure Total:</b>	<b>3731 lb</b>



Position	Elev	Angle	Ext. (cw)	Pipe	Hole	Connector	Up ( )	Ref
Rim	736.35'							
Reducer								
Invert 1	733.35'	0°	20"	12" ADS N-12	18"	Hole 18	-1.25"	P1
Invert 2								
Invert 3								
Invert 4								
Invert 5								
Invert 6								
Invert 7								
Invert 8								



**Cast (Int. Dim.) - Interior Dimensions**



Submittal Drawing  
 6/17/2025 2:20:14 PM

SUBMITTAL  
 APPROVED BY: