

Job Name: 25-1021 - 1220 N. 5TH Street
Job Location: Nashville, TN
Contractor: Hayes Pipe Supply

PC: E. Bradley
 TECH: J. Horsley
 Plant: 100



Structure ID: **CB2**
 Spec: Storm
 Type: STM.MH
 Size: 48"

Rim: 473.79'
 Invert: 465.22'
 Rim to Invert: 8.57'

Sump: 2.25"
 Floor (Top): 465.033'
 Floor Height: 6"


Floor (Bot): 464.533'
 Overall Height: 9.25'
 Slack: 0.09"

Structure Notes:


- PER ASTM C478 SPECIFICATIONS.
 - CONCRETE = 4,000 PSI AT 28 DAYS.
 - CASTING BY OTHERS (JBS 3101-V F/G/H).
- REINFORCING PER ASTM A615 (GRADE 60).
 - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W..
 - RISER/WALLS (As .12)
 - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.

STRUCTURE SUMMARY:


P5) 30" x 30" - CASTING HEIGHT - 6"	0 lb
P4) 30" x 30" - GRADE RING F/F - 3"	218 lb
P3) 48" - MH FLAT TOP w/30"x30" Hole F/G - 12"	1350 lb
P2) 48" - MH RISER T/G - 24"	1677 lb
P1) 48" - MH BASE T/n - 60"	5192 lb
1) CASTING - JBS 3101V Single Set (F/G/H)	619 lb
2) 48" - Conseal CS-102 1.00"	0 lb
1) 30" x 30" - Conseal CS-102 1.00"	0 lb
2) Hole - 22	0 lb
7) MH Step ML-10-TDS-NCR - 10"	0 lb
Structure Total:	9056 lb



Position	Elev	Angle	Pipe	Pipe OD	Hole	Connector	Up ()	Ref
Rim	473.79'							
Reducer								
Invert 1	465.22'	0°	15" RCP B WALL	19.5"	22"	Hole 22	0"	P1
Invert 2	465.42'	172°	15" RCP B WALL	19.5"	22"	Hole 22	2.375"	P1
Invert 3								
Invert 4								
Invert 5								
Invert 6								
Invert 7								
Invert 8								



Cast (Int. Dim.) - Interior Dimensions



Submittal Drawing
 2/6/2026 3:36:04 PM

SUBMITTAL
 APPROVED BY: