

**Job Name: 25-1431 - Georgetown Commons**  
**Job Location: Georgetown, KY**  
**Contractor: Winwater Hartford KY Co.**

PC: A. Chambers  
 TECH: J. Coppage  
 Plant: Beaver Dam



Structure ID: **CBI 261**  
 Spec: KYTC  
 Type: CBI TYPE A (10')  
 Size: 24" x 36"

Rim: 861.93'  
 Invert: 857.1'  
 Rim to Invert: 4.83'

Sump: 3"  
 Floor (Top): 856.85'  
 Floor Height: 8"


Floor (Bot): 856.183'  
 Overall Height: 5.667'  
 Slack: 0.96"

**Structure Notes:**


1. JR HOE KY-206 PROVIDED BY ICAST.
2. CASTING FRAME TO BE CAST INTO THE TOP PHASE.
3. PER KYTC CBI TYPE A / ASTM C478 SPEC'S.
4. CONCRETE = 4,000 PI AT 28 DAYS.
5. REINFORCING PER ASTM A615 (GRADE 60).
  - TOP PHASE (As .62) #5 BARS AT 6" C.C.E.W.
  - WALLS (As .31) #5 BARS AT 12" C.C.E.W.
  - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.

**STRUCTURE SUMMARY:**


P3) 24" x 120" - CB INLET KY A 10' TOP LEFT - 10"	3400 lb
P2) 24" x 120" - CB INLET KY A 10' BOTTOM LEFT - 18"	5270 lb
P1) 24" x 36" - BOX BASE 8inW, 8inF, Variable Ht - 32"	4104 lb
1) 24" x 36" - Conseal CS-102 1.00"	0 lb
3) Hole - 18	0 lb
1) Hole - 6	0 lb
<b>Structure Total:</b>	<b>12773 lb</b>



Position	Elev	Angle	Pipe	Pipe OD	Hole	Connector	Up ( )	Ref
Rim	861.93'							
Reducer								
Invert 1	857.1'	0°	12" HDPE	14.5"	18"	Hole 18	0"	P1
Invert 2	857.1'	90°	12" HDPE	14.5"	18"	Hole 18	0"	P1
Invert 3	857.1'	210°	12" HDPE	14.5"	18"	Hole 18	0"	P1
Invert 4	858.85'	180°	4" HDPE (perf pipe)	4.8"	6"	Hole 6	23"	P1
Invert 5								
Invert 6								
Invert 7								
Invert 8								



**Default - Interior Dimensions**



Submittal Drawing  
 4/10/2026 10:35:19 AM

SUBMITTAL  
 APPROVED BY: