

Structure ID: MH 1901

P3 BX2436-08R-VH

BOX RISER 8inW, Variable Ht T/G

P5) 24" x 120" - CB INLET KY A 10' TOP LEFT F/G - 10" P4) 24" x 120" - CB INLET KY A 10' BOTTOM LEFT T/G - 18" P3) 24" x 36" - BOX RISER 8inW, Variable Ht T/G - 35" P2) 60" x 60" - CB FT REDUCER 24"X36" HOLE T/F - 8" P1) 60" x 60" - BOX BASE 8inW, 8inF F/n - 72" 1) CASTING - HOE KY-206 F/C (KY TY1) 1) 60" x 60" - Conseal CS-102 1.00" 2) 24" x 36" - Conseal CS-102 1.00" 1) Hole - 50 1) Hole - 44 1) Hole - 30	3400 lb 5270 lb 3571 lb 3297 lb 14194 lb 206 lb 0 lb 0 lb 0 lb 0 lb 0 lb ----- Structure Total: 29938 lb
--	--



Structure Notes:
 ** KYTC STATE PROJECT **
 1. PER KYTC CBI TYPE A / ASTM C913 SPEC'S.
 2. CONCRETE = 4,000 PI AT 28 DAYS.
 3. NO INVERT CHANNEL.
 4. CASTING BY ICAST (HOE KY-206 KY TY.1 F/C)
 CAST INTO TOP SLAB.

REINFORCING PER ASTM A615 (GRADE 60).
 - TOP PHASE (As .62) #5 BARS AT 6" C.C.E.W.
 - TRANS. SLAB (As .62) #5 BARS AT 6" C.C.E.W (DBL MAT)
 - WALLS (As .31) #5 BARS AT 12" C.C.E.W.
 - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.


Rim: 878.95' Rim to Invert: 11.95' Slack: 0.4" Sump: 0" Step Position:

Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (L)	Offset
Invert 1										
Invert 2										
Invert 3										
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

RIGHT-SIDE UP VIEW (int. dimensions)



INSIDE WALL DIMENSIONS



Coating (Int):	Seam Up: Tongue Seam Dn: Groove	Wall Thickness: 8" Floor Height: 0"	Height (Int): 35" Height (Ext): 35"	Weight (Net): 3571 lb Volume (Net): 0.91cu.yd
----------------	------------------------------------	--	--	--