

Job Name: 25-1684P14 KYTC Jefferson Co. Call 200 (251007) Job Location: I-264 Louisville, Ky. Contractor: Cleary Construction, Inc.					Plant: Beaver Dam, KY 8/4/2026 11:30:12 AM		Tech: J. Coppage PC: T. Ryan														
Structure ID: 15+26 CBBI-MOD B1																					
P2		BX2436-08R-VH		BOX RISER 8inW, Variable Ht																	
P4) 24" x 120" - CASTING (cast in) - 3" P3) 24" x 120" - CB MED BAR BOX INLET 9B1 LH - 17" P2) 24" x 36" - BOX RISER 8inW, Variable Ht - 54" P1) 24" x 36" - BOX BASE 8inW, 8inF, Variable Ht - 60" 2) 24" x 36" - Conseal CS-102 1.00" 1) Hole - 22					0 lb 4000 lb 5510 lb 7263 lb 0 lb 0 lb ----- Structure Total: 16773 lb		Structure Notes: . -KYTC STATE PROJECT 251007 -REINFORCING: #5 BAR @ 12" C/C E.W. (TYP.) -CASTING FRAMES & GRATES BY OTHERS. -CS-102 BUTYL REQUIRED (SUPPLIED BY ICAST). -KYTC CERTIFICATIONS REQUIRED.														
Rim: 565.09'					Rim to Invert: 11.25'		Slack: 4"		Sump: 0"		Step Position:										
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset											
Invert 1																					
Invert 2																					
Invert 3																					
Invert 4																					
Invert 5																					
Invert 6																					
Invert 7																					
Invert 8																					
(P4) (P3) (P2) << (P1) RIGHT-SIDE UP VIEW (int. dimensions) 24" + 36" + 0° INSIDE WALL DIMENSIONS <table><tr><td>Front</td><td>Right (36")</td><td>Back (24")</td><td>Left</td><td>EXT</td></tr><tr><td colspan="4"> (P2) </td><td>54"</td></tr></table>												Front	Right (36")	Back (24")	Left	EXT	(P2)				54"
Front	Right (36")	Back (24")	Left	EXT																	
(P2)				54"																	
Coating (Int): Coating (Ext):				Seam Up: Flat Seam Dn: Groove		Wall Thickness: 8" Floor Height: 0"		Height (Int): 54" Height (Ext): 54"		Weight (Net): 5510 lb Volume (Net): 1.41cu.yd											