

Job Name: 25-1684P14 KYTC Jefferson Co. Call 200 (251007) Job Location: I-264 Louisville, Ky. Contractor: Cleary Construction, Inc.					Plant: Beaver Dam, KY 8/6/2026 2:36:50 PM		Tech: J. Coppage PC: T. Ryan				
Structure ID: 5116+07 RT DBI TYPE 1-MOD											
P1		BX3636-08BAVF			BOX BASE 8inW, 8inF, Variable Ht						
P2) 36" x 36" - P.I.P. - BY OTHERS - 8" P1) 36" x 36" - BOX BASE 8inW, 8inF, Variable Ht - 38" 1) 36" x 36" - Conseal CS-102 1.00" 1) Hole - 22					0 lb 6050 lb 0 lb 0 lb Structure Total: 6050 lb		Structure Notes: . -KYTC STATE PROJECT 251007 -REINFORCING: #5 BAR @ 12" C/C E.W. (TYP.) -FRAME & GRATES BY OTHERS. -KYTC CERTIFICATIONS REQUIRED. -#5 BAR EXTENDED OUT OF TOP OF BOX 20" AT 12" C/C.				
Rim: 567.2'		Rim to Invert: 3.9'		Slack: 0.8"		Sump: 0"		Step Position:			
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset	
Invert 1	563.3'	0°	26"	18" CMP	19"	Hole 22	22"	22"	-2"	0"	
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions) UPSIDE-DOWN VIEW (int. dimenions) STUB #5 BAR 20" OUT OF THE TOP OF THE WALLS @ 12" C-C (P2) (P1) << 36" 36" + 0°- Invert: 1 Degree: 0° Horz: 18" Hole: 22" Up(): -2" 36" 36" - 0°+ Invert: 1 Degree: 0° Horz: 18" Hole: 22" Up(): -2" INSIDE WALL DIMENSIONS (P1) Left Back (36") Right (36") Front 1 18" 8" 38" EXT 2"											
Coating (Int): Coating (Ext):			Seam Up: Flat Seam Dn: n/a		Wall Thickness: 8" Floor Height: 8"		Height (Int): 38" Height (Ext): 46"		Weight (Net): 6050 lb Volume (Net): 1.54cu.yd		