

Job Name: 25-2284C Parks at Cane Ridge Ph.2B Job Location: Antioch, TN Contractor: Josh King Excavating					Plant: Beaver Dam 6/22/2026 8:23:35 AM		Tech: S. Felletter PC: A. Chambers				
Structure ID: D1											
P1		BX036096-06W-RSVF			BOX RISER 6inW, Variable Ht F/F						
P1) 36" x 96" - BOX RISER 6inW, Variable Ht F/F - 30" 1) 36" x 96" - Conseal CS-102 1.00"						4350 lb 0 lb ----- Structure Total: 4350 lb		Structure Notes: . 1. PER ASTM C913/TDOT D-CB-14P SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. NO INVERT CHANNEL. . REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W. - WALLS (As .12) #5 BARS AT 12" C.C.E.W. - FLOOR (As .12) #5 BARS AT 12" C.C.E.W.			
Rim: 2.5'		Rim to Invert: 0'		Slack: 0"		Sump: 0"		Step Position:			
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset	
Invert 1											
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions) (P1) << 36" + 96" + 0° INSIDE WALL DIMENSIONS (P1) Front Right (96") Back (36") Left EXT 30" Coating (Int): Coating (Ext): Seam Up: Flat Seam Dn: Flat Wall Thickness: 6" Floor Height: 0" Height (Int): 30" Height (Ext): 30" Weight (Net): 4350 lb Volume (Net): 1.11cu.yd											