

Job Name: 25-2284C Parks at Cane Ridge Ph.2B Job Location: Antioch, TN Contractor: Josh King Excavating					Plant: Beaver Dam 6/22/2026 8:23:30 AM		Tech: S. Felletter PC: A. Chambers				
Structure ID: D4.2											
P1		BX2828-06R-VH			BOX RISER 6inW, Variable Ht F/F						
P1) 28" x 28" - BOX RISER 6inW, Variable Ht F/F - 27"					Structure Total: 1849 lb		Structure Notes: . 1. PER ASTM C913 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. . REINFORCING PER ASTM A615 (GRADE 60). - WALLS (As .31) #5 BARS AT 12" C.C.E.W.				
Rim: 2.25'		Rim to Invert: 0'		Slack: 0"		Sump: 0"		Step Position:			
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (⌋)	Offset	
Invert 1											
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions) (P1) << 28" 28" + 0°-											
INSIDE WALL DIMENSIONS Front Right (28") Back (28") Left (P1) EXT 27"											
Coating (Int): Coating (Ext):			Seam Up: Flat Seam Dn: Flat		Wall Thickness: 6" Floor Height: 0"		Height (Int): 27" Height (Ext): 27"		Weight (Net): 1849 lb Volume (Net): 0.47cu.yd		