

Job Name: 25-2394 McDonalds 041-1211
Job Location: Clarksville, TN
Contractor: Central Paving Co. of Paducah, Inc.

PC: Andy Chambers
 TECH: Evan Niles
 Plant: Beaver Dam, KY



Structure ID: **SCI-14**
 Spec: Storm
 Type: BX 8inW, 8inF
 Size: 24" x 36"

Rim: 537.88'
 Invert: 534.32'
 Rim to Invert: 3.56'

Sump: 0"
 Floor (Top): 534.32'
 Floor Height: 8"


Floor (Bot): 533.653'
 Overall Height: 4.208'
 Slack: 0.22"

Structure Notes:


- PER ASTM C913 SPECIFICATIONS.
- CONCRETE = 4,000 PSI AT 28 DAYS.
- NO INVERT CHANNEL.
- REINFORCING PER ASTM A615 (GRADE 60).
 - WALLS (As .12) #5 BARS AT 12" C.C.E.W.
 - FLOOR (As .12) #5 BARS AT 12" C.C.E.W.
- CASTING: JBS 3080 F/G/H BY ICAST

STRUCTURE SUMMARY:


P2) 24" x 36" - CASTING HEIGHT - 6.5"	0 lb
P1) 24" x 36" - BOX BASE 8inW, 8inF, Variable Ht F/n - 36"	4454 lb
1) CASTING - JBS 3080 SET (F/G/H)	500 lb
1) 24" x 36" - SGL 1"x14.5' Butyl	0 lb
2) Hole - 22	0 lb
Structure Total:	4954 lb



Position	Elev	Angle	Pipe	Pipe OD	Hole	Connector	Up ()	Ref
Rim	537.88'							
Reducer								
Invert 1	534.32'	315°	15" RCP B WALL	19.5"	22"	Hole 22	-2.25"	P1
Invert 2	534.32'	90°	15" RCP B WALL	19.5"	22"	Hole 22	-2.25"	P1
Invert 3								
Invert 4								
Invert 5								
Invert 6								
Invert 7								
Invert 8								



Cast (Int. Dim.) - Interior Dimensions



Submittal Drawing
 10/13/2025 4:19:40 PM

SUBMITTAL
 APPROVED BY: