

Job Name: 25-2952 - KYTC Jefferson Co Call 106 (251315) Job Location: Indiana, KY Contractor: Louisville Paving and Construction					Plant: 100 6/12/2026 3:09:58 PM		Tech: J. Horsley - A PC: J. Jarvis				
Structure ID: 58											
P1 BX2424-08BAVF BOX BASE 8inW, 8inF, Variable Ht F/n											
P3) 24" - CASTING HEIGHT - 8" P2) 24" x 24" - BX FLAT LID 8inW w/CC 24" HOLE F/F - 8" P1) 24" x 24" - BOX BASE 8inW, 8inF, Variable Ht F/n - 20" 1) 24" x 24" - Conseal CS-102 1.00" 1) 24" - Conseal CS-102 1.00" 1) Hole - 18						0 lb 770 lb 2622 lb 0 lb 0 lb 0 lb 0 lb Structure Total: 3392 lb		Structure Notes: ** KYTC STATE PROJECT ** 1. PER KYTC JB TYPE B / ASTM C-913 SPECS 2. CONCRETE: 4,000 PSI AT 28 DAYS 3. REINFORCEMENT: #5 BAR @ 12" C.C. E.W. (GRADE 60) - 2" MIN. REBAR CLEARANCE (TYP) 4. HOE KY-510 FRAME & COVER "STORM" SUPPLIED BY OTHERS			
Rim: 552' Rim to Invert: 3' Slack: 0" Sump: 0" Step Position:											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset	
Invert 1	549'	270°	20"	12" HDPE	14.5"	Hole 18	18"	18"	-3"	0"	
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
(P3) (P2) (P1) << RIGHT-SIDE UP VIEW (int. dimensions) UPSIDE-DOWN VIEW (int. dimenions) INVERT: 1 Degree: 270° Horz: 12" Hole: 18" Up(_): -3" 24" 24" - 0°+ INSIDE WALL DIMENSIONS (P1) 1 12" -3" Left Back (24") Right (24") Front 8" 20" EXT Coating (Int): Coating (Ext): Seam Up: Flat Seam Dn: n/a Wall Thickness: 8" Floor Height: 8" Height (Int): 20" Height (Ext): 28" Weight (Net): 2622 lb Volume (Net): 0.67cu.yd											