

Job Name: 25-2952 - KYTC Jefferson Co Call 106 (251315)		Plant: 100	Tech: J. Horsley - A	
Job Location: Indiana, KY Contractor: Louisville Paving and Construction		5/12/2026 1:01:38 PM	PC: J. Jarvis	
Structure ID: 77				
P2 BX024024-08LD08-14		CB FLAT TOP 8"W (HOE KY-210) F/F		
P2) 24" x 24" - CB FLAT TOP 8"W (HOE KY-210) F/F - 8" P1) 24" x 24" - BOX BASE 8inW, 8inF, Variable Ht F/n - 40" 1) This Structure Includes a Cast-in Item - HOE KY-210 Frame (Supplied By Others) 1) 24" x 24" - Conseal CS-102 1.00" 1) Hole - 18		943 lb 4340 lb 0 lb 0 lb 0 lb ----- Structure Total: 5283 lb	Structure Notes: **KYTC STATE PROJECT** 1. PER KYTC DBI TYPE 14 / ASTM C-913 SPECS 2. CONCRETE: 4,000 PSI AT 28 DAYS 3. REINFORCEMENT: #5 BAR @ 6" C.C. E.W. (GRADE 60) - 2" MIN. REBAR CLEARANCE (TYP) 4. HOE KY-210 FRAME & GRATE SUPPLIED BY OTHERS - FRAME TO BE CAST INTO FLAT LID 5. LIFTERS: 2 EA. 5CA14 CONAC A-ANCHORS FOR PLANT & FIELD HANDLING - INSTALLED AS SHOWN 6. TOP SURFACE TO RECEIVE LIGHT BRUSH FINISH	
</				

Job Number:

25-2952

Job Name:

KYTC Jefferson Co Call 106
(251315)

Structure:

77

Note:

HOE KY-210 Frame Supplied By
Others To Be Cast Into Flat Lid