

P2) 48" - MH FLAT TOP SPEC. HT. (8") SOLID - 8"	1214 lb	Structure Notes: 1. PER ASTM C478 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. REINFORCING PER TDOT DRAWING D-CB-99RB ASTM A615 (GRADE 60).
P1) 48" - MH BASE Custom Ht - 49"	4027 lb	
1) 48" - Conseal CS-102 1.00"	0 lb	
2) Hole - 32	0 lb	
	0 lb	
Structure Total:	5240 lb	
Rim: 811.8' Rim to Invert: 4.55' Slack: 0.6" Sump: 3" Step Position:		

Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset
Invert 1	807.25'	0°	0"	24" RCP B WALL	30"	Hole 32	32"	35.027"	0"	0"
Invert 2	807.25'	195°	98.698"	24" RCP B WALL	30"	Hole 32	32"	35.027"	0"	0"
Invert 3										
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

