



**Structure ID: ICAST LI2 (2)**

**P1 HWSF12**

**12" - SLOPED & FLARED HEADWALL F/F**

DIMENSIONS										
PIPE Ø	A	B	C	D	E	F	G	H	I	WEIGHT
12"	2'-8"	2'-0"	2'-0"	1'-8"	4'-0"	3"	2'	1'-8"	4'-8"	3,161 LBS.

  

**PLAN VIEW**

**ISOMETRIC VIEW  
12" HEADWALL**

  

**FRONT ELEVATION**

**SECTION A-A**

  

**NOTES:**

- CONCRETE: 4500 PS @ 28 DAYS.
- REINFORCING: #4 BAR @ 12" C/C E-W - GRADE 60, (WITH 3" CONCRETE COVER MINIMUM)
- REINFORCING BARS TO BE TACK WELDED OR TIED.
- DRAWING TO BE USED IN CONJUNCTION WITH KYTC STD. DRAWING R04H-020-03 AND THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- CHAMFER ON ALL EXPOSED EDGES.

  

PRODUCTION WORK ORDER	DESCRIPTION: KYTC 12" SLOPED & FLARED HEADWALL
QUALITY CONTROL CHECKLIST	CUSTOMER: STOCK
<input type="checkbox"/> ALL DIMENSIONS CORRECT.	PROJECT: STOCK INVENTORY
<input type="checkbox"/> LIFTERS INSTALLED.	STRUCTURE ID: N/A
<input type="checkbox"/> STEPPED IF CORRECT SIZE.	QUOTE/SALES ORDER NO: N/A
<input type="checkbox"/> REINFORCING CORRECT.	CHECK: J.H. ROSS, PE DRAWING: N. RICHARDS
<input type="checkbox"/> DISTRIBUTOR BLOCK INSTALLED.	DATE: 09/15/22 SCALE: NTS PG. 1 of 1
<input type="checkbox"/> EDGES CHAMFERED.	
<input type="checkbox"/> ALL PATCHWORK ACCEPTABLE.	

  

THIS DRAWING IS THE PROPERTY OF INFRASTRUCTURE PRECAST, INC. ANY USE OR DUPLICATION OF THIS DRAWING WITHOUT PRIOR AUTHORIZATION IS STRICTLY PROHIBITED.