

Plant: Beaver Dam

9/29/2026 2:19:01 PM

P1 CVW

WALL - EASI-SET BUILDING - WP-01 - 131" x 200"

[illegible]

Job Name: 25-3470P9 CCHS Precast Building
Job Location: 5185 Fort Campbell BLVD
Contractor: Christian County Board of Education C/O A&K Construction

Plant: Beaver Dam
9/29/2026 2:19:01 PM

Tech: J. Coppage
PC: E. Bradley



Structure ID: WP-01 - Wall Panel 1

P1 CVW

WALL - EASI-SET BUILDING - WP-01 - 131" x 200"

REINFORCING SCHEDULE

MARK #	DESCRIPTION	QTY
MK001	#3 x 3'-0"	11
MK002	#3 x 16'-6"	2
MK003	#3 x 10'-9"	2
MK004	#3 x 3'-1"	2

MESH SCHEDULE

MARK #	DESCRIPTION	QTY
M1	W4W4 4"x4" MESH 16'-6" x 10'-9"	1

REVISIONS

NO.	DESCRIPTION	DATE
1		

WORLDWIDE EASI-SET

5119 Collett Rd. • Midland, VA 22728 • info@easi-set.com
www.EasiSet.com • 800-547-4045 • Fax 540-439-2541

PROJECT: BASEBALL/SOFTBALL PRESSBOX
5185 FORT CAMPBELL BOULEVARD
HOPKINSVILLE, KY 42240
CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

SCALE: 1/8" = 1'-0"

DATE: 09/17/26

DESIGNED BY: JLB

DRAWN BY: TIL

CHECK BY: WCB

TEST DATE: 09/17/26

PIECE MARK: WP-01

NOTE:
1. CONSTRUCT REBAR-MESH CAGE ACCORDING TO THE DRAWINGS. SECURE LIFTING APPARATUS TO FORM AND ADD PROPER REINFORCEMENT. PLACE REBAR-MESH CAGE AND HARPINS AT INSERTS WITH PROPER CLEARANCES (PER DRAWINGS).

MESSAGE CENTER

1. REFER TO DETAILS AND SECTION FOR REINFORCEMENT PLACEMENT
2. SUPPLEMENTAL STEEL FOR STRIPPING AND HANDLING MAY BE ADDED AS REQUIRED.

CHECKED BY: DATE:

APPROVED BY: DATE:

REINFORCING VIEW

SCALE: 1/8" = 1'-0"

6

7

8

9