

WALL - EASI-SET BUILDING - WP-09 - 105" x 200"

[illegible]

Tech:	J. Coppage
PC:	E. Bradley



WALL - EASI-SET BUILDING - WP-09 - 105" x 200"

NOTE:
DIMENSIONS PROVIDED ARE PULLED FROM EDGE OF CAGE TO CENTERLINE OF REBAR AND TO CENTER OF REBAR TO CENTER OF REBAR

REINFORCING VIEW
SCALE: 1/2" = 1'-0"

MESSAGE CENTER

1. REFER TO DETAILS AND SECTION FOR REINFORCEMENT PLACEMENT

2. SUPPLEMENTAL STEEL FOR STRIPPING AND HANDLING MAY BE ADDED AS REQUIRED.

CHECKED BY: _____ DATE: _____

APPROVED BY: _____ DATE: _____

REINFORCING SCHEDULE

MARK #	DESCRIPTION	QTY
MK001	#3 X 3'-0"	9
MK002	#3 X 16'-6"	2
MK003	#3 X 8'-7"	2
MK004	#3 X 3'-1"	2

MESH SCHEDULE

MARK #	DESCRIPTION	QTY
M1	W40M 4"X W4F 16'-6" X 8'-7"	1

WORLDWIDE EASI-SET

5119 Caltell Rd. • Midland, VA 22728 • info@EasiSet.com

www.EasiSet.com • 800-547-4045 • Fax 540-439-2541

PROJECT: BASEBALL/SOFTBALL PRESSBOX

CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

5185 FORT CAMPBELL BOULEVARD
HOPKINSVILLE, KY 42240

REVISIONS

NO.	DESCRIPTION	DATE
1		

DATE

DATE	DESCRIPTION

ISSUED DATE
08/18/26

DESIGNED BY
TTL

CHECKED BY
MCK

SCALE
N/A

PIECE MARK
WP-09

PIECE NUMBER
104420C

NUMBER REQUIRED
2 OF 2