

**WALL - EASI-SET BUILDING - WP-09 - 110" x 120"**

[illegible]

Job Name: 25-3470P8 CCHS Precast Building  
Job Location: 5185 Fort Campbell BLVD  
Contractor: Christian County Board of Education C/O A&K Construction

Plant: Beaver Dam  
9/10/2026 9:57:20 AM

Tech: J. Coppage  
PC: E. Bradley



Structure ID: WP-09 - Wall Panel 9

P1 CVW

WALL - EASI-SET BUILDING - WP-09 - 110" x 120"

NOTE:  
DIMENSIONS PROVIDED ARE PULLED FROM EDGE OF CAGE TO CENTERLINE OF REBAR AND TO CENTER OF REBAR TO CENTER OF REBAR

REINFORCING VIEW  
SCALE: 1/4" = 1'-0"

11

10

9

8

7

6

PROJECT: 24'x50' LOCKER ROOM BUILDING  
5185 FORT CAMPBELL BOULEVARD  
HOPKINSVILLE, KY 42240  
CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

SCALE: 1/4" = 1'-0"  
DRAWN BY: JTL  
CHECK BY: JTL  
DATE: 08/17/26  
PRICE MARK: WP-09

REINFORCING SCHEDULE

| MARK # | DESCRIPTION     | QTY |
|--------|-----------------|-----|
| MK001  | #3 X 3'-0"      | 6   |
| MK002  | #3 X 9'-10"     | 6   |
| MK003  | #3 X 8'-11 1/2" | 4   |
| MK004  | #3 X 9'-6 1/2"  | 2   |
| MK005  | #3 X 3'-1"      | 4   |

MESH SCHEDULE

| MARK # | DESCRIPTION                        | QTY |
|--------|------------------------------------|-----|
| M1     | W4X4 4"x4" WVF 9'-10" X 8'-11 1/2" | 1   |

DATE: 11/11/26  
INITIALS: JTL  
REV: 1

NOTE:  
1. CONSTRUCT REBAR-MESH CAGE ACCORDING TO THE DRAWINGS. SECURE LIFTING APPARATUS TO FORM AND ADD PROPER REINFORCEMENT. PLACE REBAR-MESH CAGE AND HARPINS AT INSERTS WITH PROPER CLEARANCES (PER DRAWINGS).

1. REFER TO DETAILS AND SECTION FOR REINFORCEMENT PLACEMENT  
2. SUPPLEMENTAL STEEL FOR STRIPPING AND HANDLING MAY BE ADDED AS REQUIRED.

CHECKED BY: DATE: APPROVED BY: DATE:

PROJECT: 24'x50' LOCKER ROOM BUILDING  
5185 FORT CAMPBELL BOULEVARD  
HOPKINSVILLE, KY 42240  
CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

SCALE: 1/4" = 1'-0"  
DRAWN BY: JTL  
CHECK BY: JTL  
DATE: 08/17/26  
PRICE MARK: WP-09