



Job Name: 25-3470P9 CCHS Precast Building
Job Location: 5185 Fort Campbell BLVD
Contractor: Christian County Board of Education C/O A&K Construction

Plant: Beaver Dam
9/25/2026 2:35:31 PM

Tech: J. Coppage
PC: E. Bradley



Structure ID: WP-13 - Wall Panel 13

P1 CVW

WALL - EASI-SET BUILDING - WP-13 - 111" x 130"

REINFORCING SCHEDULE

MARK #	DESCRIPTION	QTY
MK001	#3 x 3'-0"	5
MK002	#3 x 9'-1"	2
MK003	#3 x 10'-8"	2
MK004	#3 x 3'-1"	2

MESH SCHEDULE

MARK #	DESCRIPTION	QTY
M1	WWM4 4"x4" WWF 9'-1" x 10'-8"	1

REINFORCING SCHEDULE

MARK #	DESCRIPTION	QTY
MK001	#3 x 3'-0"	5
MK002	#3 x 9'-1"	2
MK003	#3 x 10'-8"	2
MK004	#3 x 3'-1"	2

MESH SCHEDULE

MARK #	DESCRIPTION	QTY
M1	WWM4 4"x4" WWF 9'-1" x 10'-8"	1

PROJECT: BASEBALL/SOFTBALL PRESSBOX
5185 FORT CAMPBELL BOULEVARD
HOPKINSVILLE, KY 42240
CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

SCALE: 1/8"=1'-0"
DRAWN BY: JTC
CHECKED BY: EBR
DATE: 10/18/20
PRECISE MARK: WP-13

PROJECT: BASEBALL/SOFTBALL PRESSBOX
5185 FORT CAMPBELL BOULEVARD
HOPKINSVILLE, KY 42240
CONTRACTOR: CHRISTIAN COUNTY SCHOOLS

NOTE:
1. CONSTRUCT REBAR-MESH CAGE
ACCORDING TO THE DRAWINGS. SECURE
LIFTING APPARATUS TO FORM AND ADD
PROPER REINFORCEMENT. PLACE
REBAR-MESH CAGE AND HARPPINS AT
INSERTS WITH PROPER CLEARANCES
(PER DRAWINGS).

SALES ORDER NUMBER: 103442C
BUILDING: 2 OF 2
SHEET NUMBER: 2

MESSAGE CENTER

1. REFER TO DETAILS AND SECTION
FOR REINFORCEMENT PLACEMENT

2. SUPPLEMENTAL STEEL FOR
STRIPPING AND HANDLING MAY BE
ADDED AS REQUIRED.

CHECKED BY: DATE:
APPROVED BY: DATE:

REINFORCING VIEW

SCALE: 1/2" = 1'-0"