

Job Name: 25-4490P2 Heartland Meadows Subdivision Job Location: Elizabethtown, KY 40165 Contractor: Kauffeld Brothers Construction					Plant: 100 7/30/2026 10:22:32 AM		Tech: Jared - A PC: Celina Goff			
Structure ID: CI 1-11 (23)										
P1 BX24300808VF			BOX BASE 8inW, 8inF, Variable Ht							
P3) 24" x 30" - CASTING HEIGHT - 6" P2) 24" x 30" - BOX RISER 8inW, Variable Ht - 12" P1) 24" x 30" - BOX BASE 8inW, 8inF, Variable Ht - 41" 1) CASTING - HOE 360 L Vane Set (F/G/H) 2) 24" x 30" - Conseal CS-102 1.00" 2) Hole - 30"					0 lb 1128 lb 4377 lb 362 lb 0 lb 0 lb ----- Structure Total: 5866 lb		Structure Notes: 1. HOE 360 FLAT SET PROVIDED BY ICAST. 2. PER ASTM C913 SPECIFICATIONS. 3. CONCRETE = 4,000 PSI AT 28 DAYS. 4. NO INVERT CHANNEL. 5. REINFORCING PER ASTM A615 (GRADE 60). - WALLS (As .12) #5 BARS AT 12" C.C.E.W. - FLOOR (As .12) #5 BARS AT 12" C.C.E.W. 6. PLEASE VERIFY THE CURB LINE LOCATION AND THE ORIENTATION OF THE BOX.			
Rim: 863.96' Rim to Invert: 4.98' Slack: 0.76" Sump: 0" Step Position:										
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset
Invert 1	858.98'	270°	23"	24" HDPE	27.8"	Hole 30	30"	30"	-1.9"	0"
Invert 2	858.98'	90°	23"	24" HDPE	27.8"	Hole 30	30"	30"	-1.9"	0"
Invert 3										
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

RIGHT-SIDE UP VIEW (int. dimensions)

UPSIDE-DOWN VIEW (int. dimensions)

INSIDE WALL DIMENSIONS

Coating (Int): Coating (Ext):	Seam Up: Tongue Seam Dn: n/a	Wall Thickness: 8" Floor Height: 8"	Height (Int): 41" Height (Ext): 49"	Weight (Net): 4377 lb Volume (Net): 1.12cu.yd
----------------------------------	---------------------------------	--	--	--