

Plant: Beaver Dam
9/16/2026 3:43:58 PM



P1 CVW

WALL - EASI-SET BUILDING - WP-03 - 85" x 120"

EASI-SET® WORLDWIDE

www.EasiSet.com • 800-547-4045 • Fax 540-439-2641
5119 Callett Rd. • Midland, VA 22728 • info@EasiSet.com

BILL OF MATERIALS

MARK #	DESCRIPTION	QTY
P103G	2 TON R-4 TECH EJECTION ANCHOR (762759) (GALV)	2
P201G	4"x4"x1/2"W/(2) 3/8"x1 1/2" H.A.S. W/ 1"-4" BENT REBAR (GALV)	6
P108P	P15T 1" NC THREADED INSERT	16

HANDLING INSTRUCTIONS

SHIPPING TILT TABLE

YARD STORAGE

CONCRETE - INSTRUCTIONS

CONCRETE RELEASE - 2,500 P.S.I.
CONCRETE @ 28 DAYS - 5,000 P.S.I.

CONCRETE MIXES

MIX	VOLUME	C.Y.
CONCRETE - GRAY	-	0.83
CONCRETE - MK 1	-	C.Y.
CONCRETE - MK 2	-	C.Y.
SFET SOUND	-	C.Y.
TOTALS	-	0.83 C.Y.

WEIGHT: 3,390 LBS.

FINISHING INSTRUCTIONS

F₁₅ = HORIZONTAL LAP
F₁₆ = FORM FINISH
F₁₇ = HARD TROMEL FINISH

SOFT (L.F.) = 63.79
SOFT (U.F.) = --
SOFT (L.F.) = --
SOFT (U.F.) = --

CONTROL NUMBERS:

PRODUCT	SALES ORDER NUMBER	DATE
BUILDING	47334	DATE
SHEET NUMBER	WP-403	DATE

PROJECT: 10' x 26' x 9'-11"

CITY PARK IMPROVEMENTS-PHASE II
CITY OF LATHROP, MISSOURI
VENSTRA & KIMM INC.

MESSAGE CENTER

1. REFER TO DETAILS AND SECTION FOR REINFORCEMENT PLACEMENT
2. SHOP TICKET SHOWS EXTERIOR FINISH CAST FACE DOWN (B.I.F.)

FORM VIEW
SCALE: 1/8" = 1'-0"

WINDOW DETAIL

DETAILS AND SECTION FOR REINFORCEMENT PLACEMENT

SHOP TICKET SHOWS EXTERIOR FINISH CAST FACE DOWN (B.I.F.)

Job Name: 25-4520 - City Park Improvments
Job Location: Lathrop, MO
Contractor: Sands Construction Company

Plant: Beaver Dam

Tech: J. Coppage

9/16/2026 3:43:58 PM

PC: E. Bradley



Structure ID: WP-03a - Wall Panel 3

P1 CVW

WALL - EASI-SET BUILDING - WP-03 - 85" x 120"

