



Structure ID: 8.1 (5)

P1 HWSF12

12" - SLOPED & FLARED HEADWALL F/F

| DIMENSIONS | | | | | | | | | | |
|------------|-------|-------|-------|-------|-------|----|----|-------|-------|------------|
| PIPE Ø | A | B | C | D | E | F | G | H | I | WEIGHT |
| 12" | 2'-8" | 2'-0" | 2'-0" | 1'-8" | 4'-0" | 3" | 2' | 1'-8" | 4'-8" | 3,161 LBS. |

NOTES:

- CONCRETE: 4500 PS @ 28 DAYS.
- REINFORCING: #4 BAR @ 12" C/C E-W - GRADE 60, (WITH 3" CONCRETE COVER MINIMUM)
- REINFORCING BARS TO BE TACK WELDED OR TIED.
- DRAWING TO BE USED IN CONJUNCTION WITH KYTC STD. DRAWING RMH-020-03 AND THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- CHAMFER ON ALL EXPOSED EDGES.

| | |
|-----------------------------|--|
| PRODUCT I.D.: HWSF12 | DESCRIPTION: KYTC 12" SLOPED & FLARED HEADWALL |
| PRODUCT VIEW: RIGHT SIDE UP | CUSTOMER: STOCK |
| PLANT: BEAVER DAM, KY. | PROJECT: STOCK INVENTORY |
| WEIGHT: 3,161 LBS. | STRUCTURE I.D.: N/A |
| TOP SECTION JOINT: N/A | QUOTE/SALES ORDER NO: N/A |
| BASE SECTION JOINT: N/A | CHECK: J.H. ROSS, PE DRAWING: N. RICHARDS |
| QC CHECK INITIALS: | DATE: 09/15/22 SCALE: NTS FIG. 1 of 1 |

PRODUCTION WORK ORDER

QUALITY CONTROL CHECKLIST

- ALL DIMENSIONS CORRECT.
- LIFTERS INSTALLED.
- STEPPED HF CORRECT SIZE.
- REINFORCING CORRECT.
- DISTRIBUTOR BLOCK INSTALLED.
- EDGES CHAMFERED.
- ALL PATCHWORK ACCEPTABLE.

THIS DRAWING IS THE PROPERTY OF INFRASTRUCTURE PRECAST, INC. ANY USE OR DUPLICATION OF THIS DRAWING WITHOUT PRIOR AUTHORIZATION IS STRICTLY PROHIBITED.