

Job Name: 26-1000P2 Clark Distributing New HQ - Site Structures Job Location: Bowling Green, KY Contractor: Scotty's Contracting & Stone, LLC					Plant: Beaver Dam 8/7/2026 10:38:44 AM		Tech: S. Felletter PC: M. Sullivan				
Structure ID: DBI-11											
P1		BX3648-08BAVF			BOX BASE 8inW, 8inF, Variable Ht F/n						
P2) 36" x 48" - CASTING HEIGHT - 0" P1) 36" x 48" - BOX BASE 8inW, 8inF, Variable Ht F/n - 70" 1) CASTING - HOE 918 F/G 1) 48" x 48" - Conseal CS-102 1.00" 1) Hole - 44 1) Hole - 18 1) Hole - 38 6) MH Step ML-10-TDS-NCR - 10"					0 lb 9679 lb 228 lb 0 lb 0 lb 0 lb 0 lb 0 lb 9907 lb		Structure Notes: 1. PER ASTM C913 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. CASTING BY ICAST (HOE 918 F/G). REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W. - WALLS (As .31) #5 BARS AT 12" C.C.E.W. - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.				
Rim: 587.66' Rim to Invert: 5.87' Slack: 0.44' Sump: 0" Step Position: 0°											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset	
Invert 1	581.79'	90°	32"	36" HDPE	41.7"	Hole 44	44"	44"	-2.85"	0"	
Invert 2	581.79'	180°	26"	15" PVC SDR35	15.3"	Hole 18	18"	18"	-0.15"	0"	
Invert 3	581.79'	270°	32"	30" HDPE	35.1"	Hole 38	38"	38"	-2.55"	0"	
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions) 					UPSIDE-DOWN VIEW (int. dimenions) 						
(P1) << 					INSIDE WALL DIMENSIONS 						
Coating (Int): Coating (Ext):			Seam Up: Flat Seam Dn: n/a		Wall Thickness: 8" Floor Height: 8"		Height (Int): 70" Height (Ext): 78"		Weight (Net): 9679 lb Volume (Net): 2.47cu.yd		