

Job Name: 26-1322 - KYTC Warren Co (261503) Job Location: Bowling Green, KY Contractor: Mick-Murf Construction Inc.					Plant: 100 9/7/2026 11:06:04 AM		Tech: Jared - F PC: C. Goff					
Structure ID: 16-24 DBI3												
P1 BX3636-08BAVF			BOX BASE 8inW, 8inF, Variable Ht F/n									
P2) 36" x 36" - P.I.P. - BY OTHERS - 8" P1) 36" x 36" - BOX BASE 8inW, 8inF, Variable Ht F/n - 35" 1) 36" x 36" - Conseal CS-102 1.00" 1) Hole - 28 1) Hole - 18						0 lb 5366 lb 0 lb 0 lb 0 lb ----- 5366 lb		Structure Notes: ** KYTC STATE PROJECT ** 1. PER KYTC DBI TYPE 3 / ASTM C913 SPEC'S. 2. CONCRETE = 4,000 PI AT 28 DAYS. 3. STUB #5 BARS 20" OUT TOP OF WALLS (SPA@12"C/C) 4. CASTING SUPPLIED BY OTHERS (HOE KY-328 SET (DBI 3)). REINFORCING PER ASTM A615 (GRADE 60). - WALLS (As .31) #5 BARS AT 12" C.C.E.W. - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.				
Rim: 531.77' Rim to Invert: 3.89' Slack: 3.68" Sump: 0" Step Position:												
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset		
Invert 1	527.88'	0°	26"	24" CMP	25"	Hole 28	28"	28"	-2"	0"		
Invert 2	527.96'	270°	26"	15" CMP	16"	Hole 18	18"	18"	-0.5"	0"		
Invert 3												
Invert 4												
Invert 5												
Invert 6												
Invert 7												
Invert 8												

RIGHT-SIDE UP VIEW (int. dimensions)

#5 DOWELS @ 12" O.C. STUBBED 20" OUT THE TOP OF THE WALLS

UPSIDE-DOWN VIEW (int. dimensions)

INSIDE WALL DIMENSIONS

Coating (Int): Coating (Ext):	Seam Up: Flat Seam Dn: n/a	Wall Thickness: 8" Floor Height: 8"	Height (Int): 35" Height (Ext): 43"	Weight (Net): 5366 lb Volume (Net): 1.37cu.yd
----------------------------------	-------------------------------	--	--	--