

Job Name: 26-1822 - Project Versailles Job Location: Versailles, KY Contractor: KY Earthworks					Plant: 100 9/24/2026 11:31:22 AM		Tech: Jared - F PC: E. Bradley				
Structure ID: F4.1 ST-CI											
P1		MH060BA60		MH BASE T/n							
P4) 24" x 36" - CASTING HEIGHT - 6" P3) 60" - MH FLAT TOP w/24"x36" Hole F/G - 13" P2) 60" - MH RISER T/G - 24" P1) 60" - MH BASE T/n - 60" 1) CASTING - HOE 525 LV SET (F/G/H) 2) 60" - Conseal CS-102 1.00" 1) 24" x 36" - Conseal CS-102 1.00" 1) Hole - 48 1) Hole - 16 1) Hole - 40 7) MH Step ML-10-TDS-NCR - 10"					0 lb 3499 lb 2505 lb 7186 lb 442 lb 0 lb 0 lb 0 lb 0 lb 0 lb 0 lb		Structure Notes: 1. PER ASTM C478 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. NO INVERT CHANNEL. 4. CASTING BY ICAST (HOE 525 LV SET (F/G/H)). REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W.. - RISER/WALLS (As .18) - FLOOR (As .37) #5 BARS AT 10" C.C.E.W.				
Structure Total:					13632 lb						
Rim: 934.75' Rim to Invert: 8.41' Slack: 1.92' Sump: 4" Step Position: 270											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset	
Invert 1	926.34'	0°	0"	36" RCP B WALL	44"	Hole 48	48"	55.638"	0"	0"	
Invert 2	926.44'	105°	66"	12" HDPE	14.5"	Hole 16	16"	16.196"	4"	0"	
Invert 3	926.34'	195°	122.5"	30" RCP B WALL	37"	Hole 40	40"	43.784"	0.5"	0"	
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											

RIGHT-SIDE UP VIEW (int. dimensions)

UPSIDE-DOWN VIEW (int. dimensions)

INSIDE WALL DIMENSIONS

Coating (Int): Coating (Ext):	Seam Up: Tongue Seam Dn: n/a	Wall Thickness: 6" Floor Height: 8"	Height (Int): 60" Height (Ext): 68"	Weight (Net): 7186 lb Volume (Net): 1.84cu.yd
----------------------------------	---------------------------------	--	--	--