

Job Name: 26-1822 - Project Versailles Job Location: Versailles, KY Contractor: KY Earthworks					Plant: 100		Tech: Jared - F			
					9/25/2026 3:06:31 PM		PC: E. Bradley			
Structure ID: F9 DBI11										
P1 MH060BAVF			MH BASE Custom Ht F/n							
P3) 24" x 30" - CASTING HEIGHT - 3.75" P2) 60" - MH FLAT TOP w/24"x30" Hole F/F - 8" P1) 60" - MH BASE Custom Ht F/n - 38" 1) CASTING - HOE KY-460-11 F/G (DBI 11) 1) 60" - Conseal CS-102 1.00" 1) 24" x 30" - Conseal CS-102 1.00" 2) DOGHOUSE INVRTD - 40"x37" 1) DOGHOUSE INVRTD - 32"x31"						0 lb 2250 lb 3645 lb 421 lb 0 lb 0 lb 0 lb 0 lb 0 lb ----- Structure Total: 6315 lb		Structure Notes: 1. PER ASTM C478 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. NO STEPS AND NO INVERT CHANNEL. 4. CASTING BY ICAST (HOE KY-460-11 F/G (DBI 11)). . REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W. - RISER/WALLS (As .18) - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.		
Rim: 933.04' Rim to Invert: 3.87' Slack: 0.19" Sump: 3.5" Step Position:										
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset
Invert 1	929.17'	0°	0"	30" RCP B WALL	37"	DOGHOUSE INVRTD 40"x37"	40" x 37"	43.784"	0"	0"
Invert 2	929.67'	95°	59.75"	24" RCP B WALL	30"	DOGHOUSE INVRTD 32"x31"	32" x 31"	33.752", 1.312"	6.5"	0"
Invert 3	929.17'	184°	115.625"	30" RCP B WALL	37"	DOGHOUSE INVRTD 40"x37"	40" x 37"	43.784", 133.105"	0"	0"
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

RIGHT-SIDE UP VIEW (int. dimensions)

UPSIDE-DOWN VIEW (int. dimensions)

INSIDE WALL DIMENSIONS

Coating (Int):	Seam Up: Flat	Wall Thickness: 6"	Height (Int): 38"	Weight (Net): 3645 lb
Coating (Ext):	Seam Dn: n/a	Floor Height: 8"	Height (Ext): 46"	Volume (Net): 0.93cu.yd