

Job Name: 26-1852 - Oakland City CCMG Job Location: Oakland City, IN Contractor: SAMM Trucking & Excavating, Inc.				Plant: 100 7/15/2026 12:46:34 PM		Tech: J. Horsley PC: J. Jarvis					
Structure ID: QL7 INE7 - Mill & Jackson Street											
P1		BX3030-06W08F-BAVF			BOX BASE 6inW, 8inF, Variable Ht F/n						
P2) 30" x 30" - CASTING HEIGHT - 0" P1) 30" x 30" - BOX BASE 6inW, 8inF, Variable Ht F/n - 37" 1) 30" x 30" - SGL 1"x14.5' Butyl 1) Hole - 20					0 lb 3708 lb 0 lb 0 lb ----- 3708 lb		Structure Notes: 1. INDOT INLET TYPE E / ASTM C913 SPEC'S. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. CASTING (HOE R-4215C GRATE) BY ICAST. 4. RECESS/GRATE SEAT (34.5"x34.5"x1" DEEP) IN TOP OF WALLS. REINFORCING PER ASTM A615 (GRADE 60). - WALLS (As .31) #5 BARS AT 12" C.C.E.W. - FLOOR (As .31) #5 BARS AT 12" C.C.E.W.				
Rim: 3' Rim to Invert: 3' Slack: 0.296" Sump: 1.296" Step Position:											
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up ()	Offset	
Invert 1	0'	0°	21"	15" HDPE	17.6"	Hole 20	20"	20"	0"	0"	
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions)					UPSIDE-DOWN VIEW (int. dimensions)						
INSIDE WALL DIMENSIONS											
Coating (Int): Coating (Ext):				Seam Up: Flat Seam Dn: n/a		Wall Thickness: 6" Floor Height: 8"		Height (Int): 37" Height (Ext): 45"		Weight (Net): 3708 lb Volume (Net): 0.95cu.yd	