

Job Name: 26-2030 - KYTC McCracken Co. Call 111 (ID 264505)

Job Location: Paducah, KY

Contractor: Jim Smith Contracting Co, LLC

Plant: 100

6/12/2026 7:50:16 AM

Tech: J. Horsley

PC: J. Jarvis



Structure ID: 151+22 LT S-2 CBIB

P2 BX2424-08R24

BOX RISER 8inW F/G

P5) 8" x 120" - CB INLET KY B 10' TOP F/G - 9"

P4) 24" x 120" - CB INLET KY B 10' BOTTOM RIGHT T/G - 17"

P3) 24" x 24" - FIELD ADJUSTMENT - 3"

P2) 24" x 24" - BOX RISER 8inW F/G - 24"

P1) 24" x 24" - BOX BASE 8inW, 8inF, Variable Ht T/n - 44"

1) CASTING - HOE KY-345 SET (CBI B)

2) 24" x 24" - Conseal CS-102 1.00"

1) Hole - 18

1660 lb

2650 lb

0 lb

2062 lb

4684 lb

290 lb

0 lb

0 lb

11346 lb

Structure Notes:

** KYTC STATE PROJECT **

1. PER KYTC CBI TYPE B / ASTM C913 SPEC'S.

2. CONCRETE = 4,000 PI AT 28 DAYS.

3. CASTING BT ICAST (HOE KY-345 F/G(CBI-B)

.

REINFORCING PER ASTM A615 (GRADE 60).

- TOP PHASE (As .62) #5 BARS AT 6" C.C.E.W.

- WALLS (As .31) #5 BARS AT 12" C.C.E.W.

- FLOOR (As .31) #5 BARS AT 12" C.C.E.W.

Rim: 374.92'

Rim to Invert: 8.11'

Slack: 0.32"

Sump: 0"

Step Position:

Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (┘)	Offset
Invert 1										
Invert 2										
Invert 3										
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

(P5)

(P4)

(P3)

(P2) <<

(P1)

RIGHT-SIDE UP VIEW (int. dimensions)

24"

+

24"

+ 0°-

INSIDE WALL DIMENSIONS

Front

Right (24")

Back (24")

Left

(P2)

24"

Coating (Int):

Coating (Ext):

Seam Up: Flat

Seam Dn: Groove

Wall Thickness: 8"

Floor Height: 0"

Height (Int): 24"

Height (Ext): 24"

Weight (Net): 2062 lb

Volume (Net): 0.53cu.yd