

Job Name: 26-3367 ADS Paddocks of Parkridge Sec.2 Job Location: Louisville, KY Contractor: ADS Advanced Drainage Systems, Inc.						Plant: Beaver Dam 8/26/2026 10:19:53 AM		Tech: S. Felletter PC: M. Sullivan			
Structure ID: WQU											
P3		MH060RSVF		MH RISER Custom Ht T/G							
P5) 24" - CASTING HEIGHT - 7" P4) 60" - MH FLAT TOP w/24" Ctr. Hole F/G - 13" P3) 60" - MH RISER Custom Ht T/G - 69" P2) 60" - MH RISER SPECIAL T/G - 72" P1) 60" - MH BASE Custom Ht T/n - 25" 1) ASSEMBLY REQUIRED 1) JOINT WRAP - 0.065"x6"x50' CONSEAL CS212 1) JOINT WRAP PRIMER - CONSEAL CS-75 (1 gal.) 1) CASTING - HOE MC-375 F/C Storm 3) 60" - Conseal CS-102 1.00" (Double) 1) 24" - Conseal CS-102 1.00" (Double) 2) Hole - 16						0 lb 2674 lb 7203 lb 7312 lb 5343 lb 0 lb 0 lb 0 lb 271 lb 0 lb 0 lb 0 lb Structure Total: 22803 lb		Structure Notes: 1. PER ASTM C478 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. CASTING BY ICAST (HOE MC-375 F/C "STORM"). 4. LIFTING ANCHORS TO BE INSTALLED ON THE OUTSIDE OF THE STRUCTURE. . REINFORCING PER ASTM A615 (GRADE 60). - TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W. - RISER/WALLS (As .18) - FLOOR (As .37) #5 BARS AT 10" C.C.E.W.			
Rim: 479.17'		Rim to Invert: 8.75'		Slack: 0"		Sump: 81"		Step Position: 0°			
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (⌋)	Offset	
Invert 1											
Invert 2											
Invert 3											
Invert 4											
Invert 5											
Invert 6											
Invert 7											
Invert 8											
RIGHT-SIDE UP VIEW (int. dimensions)											
INSIDE WALL DIMENSIONS											
Coating (Int): Coating (Ext):			Seam Up: Tongue Seam Dn: Groove		Wall Thickness: 6" Floor Height: 0"		Height (Int): 69" Height (Ext): 69"		Weight (Net): 7203 lb Volume (Net): 1.84cu.yd		