

Job Name: 26-3522 ADS Miller-Blankenbaker Rd. Subdivision

Job Location: Jeffersontown, KY

Contractor: ADS Advanced Drainage Systems, Inc.

Plant: Beaver Dam

9/3/2026 2:23:57 PM

Tech: S. Felletter

PC: M. Sullivan

INFRASTRUCTURE

ICAST

PRECAST

Structure ID: STR-19

P2 MH036RS60

MH RISER T/G

P6) 24" - CASTING HEIGHT - 7"

P5) 24" - GRADE RING F/F - 3"

P4) 36" - MH FLAT TOP w/ 24" Ctr. Hole F/G - 10"

P3) 36" - MH RISER T/G - 36"

P2) 36" - MH RISER T/G - 60"

P1) 36" - MH BASE T/n - 18"

1) JOINT WRAP - 0.065"x6"x50' CONSEAL CS212

1) JOINT WRAP PRIMER - CONSEAL CS-75 (1 gal.)

1) ASSEMBLY REQUIRED

1) CASTING - HOE MC-375 F/C Storm

3) 36" - Conseal CS-102 1.00" (Double)

2) 24" - Conseal CS-102 1.00" (Double)

2) Hole - 12

0 lb

202 lb

896 lb

1518 lb

2454 lb

1525 lb

0 lb

0 lb

0 lb

271 lb

0 lb

0 lb

0 lb

6867 lb

Structure Notes:

1. PER ASTM C478 SPECIFICATIONS.

2. CONCRETE = 4,000 PSI AT 28 DAYS.

3. LIFTING ANCHORS TO BE INSTALLED ON THE OUTSIDE OF THE STRUCTURE

4. CASTING BY ICAST (HOE MC-375 F/C "STORM").

.

REINFORCING PER ASTM A615 (GRADE 60).

- TOP SLAB (As .62) #5 BARS AT 6" C.C.E.W.

- RISER/WALLS (As .12)

- FLOOR (As .31) #5 BARS AT 12" C.C.E.W.

Structure Total:

6867 lb

Rim: 710.75'

Rim to Invert: 6.65'

Slack: 0.76"

Sump: 54.96"

Step Position:

Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (⌋)	Offset
Invert 1	704.1'	0°	0"	8" HDPE	9.1"	Hole 12	12"	12.234"	31.46"	0"
Invert 2	704.1'	307°	117.88"	8" HDPE	9.1"	Hole 12	12"	12.234"	31.46"	0"
Invert 3										
Invert 4										
Invert 5										
Invert 6										
Invert 7										
Invert 8										

(P6)

(P5)

(P4)

(P3)

(P2) <<

(P1)

RIGHT-SIDE UP VIEW (int. dimensions)

+ 0°-

Invert: 1

Degree: 0°

Horz: 0"

Hole: 12"

Up(⌋): 31.46"

Invert: 2

Degree: 307°

Horz: 96.447"

Hole: 12"

Up(⌋): 31.46"

INSIDE WALL DIMENSIONS

0°

90°

180°

270°

360°

0"

96.447"

31.46"

31.46"

1

2

(P2)

60"

Coating (Int):

Coating (Ext):

Seam Up: Tongue

Seam Dn: Groove

Wall Thickness: 4"

Floor Height: 0"

Height (Int): 60"

Height (Ext): 60"

Weight (Net): 2454 lb

Volume (Net): 0.63cu.yd