



Job Name: 26-3533 - Redemption Christian Church Job Location: Tell City, IN Contractor: Lutgring Bros, Inc.					Plant: 100 10/1/2026 2:23:48 PM		Tech: Jared - F PC: A. Chambers								
Structure ID: AD202															
P1		BX2424-08B36-KO		KNOCKOUT BASE 8"W/F - STOCK											
P2) 24" x 24" - CASTING HEIGHT - 4" P1) 24" x 24" - KNOCKOUT BASE 8"W/F - STOCK - 36" 1) CASTING - HOE 280T F/G 1) 24" x 24" - Conseal CS-102 1.00"						0 lb 2564 lb 182 lb 0 lb ----- Structure Total: 2746 lb		Structure Notes: . 1. PER ASTM C913 SPECIFICATIONS. 2. CONCRETE = 4,000 PSI AT 28 DAYS. 3. NO STEPS AND NO INVERT CHANNEL. 4. CASTING BY ICAST (HOE-280T(F/G)). 5. PIPE OPENINGS TO BE CORED IN THE FIELD BY OTHERS. . REINFORCING PER ASTM A615 (GRADE 60). - WALLS (As .12) #5 BARS AT 12" C.C.E.W. - FLOOR (As .12) #5 BARS AT 12" C.C.E.W.							
Rim: 582.5'		Rim to Invert: 0'		Slack: 0"		Sump: 40"		Step Position:							
Position	Elev	Angle	Ext. (cw)	Pipe	Pipe OD	Connector	Hole	Horz Size	Up (_)	Offset					
Invert 1															
Invert 2															
Invert 3															
Invert 4															
Invert 5															
Invert 6															
Invert 7															
Invert 8															
RIGHT-SIDE UP VIEW (int. dimensions)						UPSIDE-DOWN VIEW (int. dimenions)									
															
INSIDE WALL DIMENSIONS															
						Front		Right (24")		Back (24")		Left		EXT	
(P1)														36"	
														8"	
Coating (Int): Coating (Ext):				Seam Up: Flat Seam Dn: n/a		Wall Thickness: 8" Floor Height: 8"		Height (Int): 36" Height (Ext): 44"		Weight (Net): 2564 lb Volume (Net): 0.66cu.yd					