



981 W. 7th Street
 Beaver Dam, KY 42320
 270-363-2234

infrastructure precast, inc.

Take Off By: 3/19/2019 Nathan

Notes:

Structure: 4' MH Flat Lid 24" Centered No Groove

Job Number:

Job Name: INVENTORY

Job Location:

Specification: Custom

Contractor:

Channel:

Based on:

Dimension Tolerances

Length, Width, Height, Wall Thickness: $\pm 3/4"$


Rebar Spacing: $\pm 1"$

Concrete Cover over Reinforcing: $> 1/2"$

Hole Size: $\pm 1/2"$

Plan View

→ A



↳ A

Opening Schedule

ID	Hole Ref.	Pipe Size	Hole Size	Connector	Angle

BOM For Stack

ID	Description	Qty.	Weight	Shop
A	48" Flat Top No Groove 24" Conc 8T 7.0H	1	1,439	
Totals (precast, lbs)		1	1,439	

Elevation (View A-A)

Part Description: 48" Flat Top No Groove 24" Conc 8T 7.0H

A

