





Quotation - Structure List

Project Name
Phase 2 I&I Rehabilitation

Location, State, Zip
Marion County, Bradfordsville, KY 40009

Quote Product Legend:						Quote #
Option #	Joint Sealant	Ext. Jt. Wrap	Special Admixtures	Coatings	Pipe Connection Type	
1	1" CS-102	6" CS-212	None	CS-55 (Exterior)	Grout	26-3257Y
2	1" CS-102 Double	12" CS-212	Xypex*	Carboline 300M (Exterior)	Boot	
3	1.25" CS-102	12" MacWrap	Conshield*	Masterseal 610 (Exterior)	A-Lok	
4	1.25" CS-102 Double	9" Infi-Shield	Xypex & Conshield*	HLM 5000 (Exterior)	Link Seal (By Others)	Date of Quote
5	1" CS-231		Xypex Bio-San C500*	CS-55 (Interior)		8/4/2026
6	1" CS-231 Double		*Or Approved Alt.	Carboline 300M (Interior)		
7	1.25" CS 231			Masterseal 610 (Interior)		
8	1.25" CS 231 Double			HLM 5000 (Interior)		Version
9	3/4" CS-440					1Y
10	HK TSS Gasket					

Structure Information									Accessories					Structure Configuration (See Legend)										Item Totals		
Item	Bid Item #	Structure #	Unit of Measure	Line Item Description	Structure ID Inches	Structure Total Depth Ft.	Quantity	Structure Price Per	Casting or Hatch Model Number	Casting or Hatch Qty	Casting or Hatch Price Per Unit	Accessory Type	Accessory Qty	Accessory Price (Per Str.)	Joint Sealant	Exterior Wrap	Spc. Admixture	Invert Channel	Open Bottom (OB) or Open Top (OT)	Extended Base Slab	Coatings	Pipe Connection Type	See Notes	Item Unit Price	Extended Item Total	
2		MH-A-1 SS-MH	EA	Sanitary Manhole	48 Dia.	10.67	1	\$3,268	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,763	\$3,763	
3		MH-A-2 SS-MH	EA	Sanitary Manhole	48 Dia.	7.60	1	\$2,771	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,266	\$3,266	
4		MH-A-3 SS-MH	EA	Sanitary Manhole	48 Dia.	6.75	1	\$2,635	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,130	\$3,130	
5		MH-A-4 SS-MH	EA	Sanitary Manhole	48 Dia.	4.73	1	\$2,283	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$2,778	\$2,778	
6		MH-B-1 SS-MH	EA	Sanitary Manhole	48 Dia.	6.20	1	\$2,397	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$2,892	\$2,892	
7		MH-I-2 SS-MH	EA	Sanitary Manhole	48 Dia.	6.00	1	\$2,353	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$2,848	\$2,848	
8		MH-I-3 SS-MH	EA	Sanitary Manhole	48 Dia.	7.20	1	\$2,566	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,061	\$3,061	
9		MH-I-4 SS-MH	EA	Sanitary Manhole	48 Dia.	8.20	1	\$2,745	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,240	\$3,240	
10		MH-I-4A SS-MH	EA	Sanitary Manhole	48 Dia.	7.53	1	\$2,689	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$3,184	\$3,184	
11		MH-I-4A1 SS-MH	EA	Sanitary Manhole	48 Dia.	5.95	1	\$2,361	HOE MC-375 F/C "Sanitary"	1	\$495				2	1	No	Yes	No		No	2		\$2,856	\$2,856	
			Structures Subtotal:				\$26,068.00		Casting/Hatch Subtotal:			\$4,950.00		Accessory Subtotal:		\$0.00		Structures, Casting/Hatch, Accessory Subtotal:							\$31,018.00	

This quote is CONFIDENTIAL and is intended only for parties who received it from Infrastructure Precast, Inc., and shall not be disclosed to, nor discussed with, any third parties.

Job Notes:



Infrastructure Precast, Inc.
Mailing Address: PO Box 27, Hartford, KY 42347
Production Facility: 981 W 7th St, Beaver Dam, KY 42320
Corporate Office: 552 St Rt 69 N, Hartford, KY 42347
Office: (270) 363-2238
sales@icastinc.com
Web Site: icastinc.com

Project Name: Phase 2 I&I Rehabilitation
Project Address: KY 337
Location, State, Zip: Marion County, Bradfordsville, KY 40009
Project Owner: n/a
Storm End User: n/a
Sanitary End User: n/a
Project Engineer: Kenvirons

Quotation - Terms & Conditions (Page 1 of 2)		
Quote #	Date of Quote	Version
26-3257Y	8/4/2026	1Y
Terms	FOB	Valid (days)
Net 30	Jobsite	30



Infrastructure Precast, Inc.
Mailing Address: PO Box 27, Hartford, KY 42347
Production Facility: 981 W 7th St, Beaver Dam, KY 42320
Corporate Office: 552 St Rt 69 N, Hartford, KY 42347
Office: (270) 363-2238
sales@icastinc.com
Web Site: icastinc.com

Project Name: Phase 2 I&I Rehabilitation
Project Address: KY 337
Location, State, Zip: Marion County, Bradfordsville, KY 40009
Project Owner: n/a
Storm End User: n/a
Sanitary End User: n/a
Project Engineer: Kenvirons

Quotation - Terms & Conditions (Page 2 of 2)

Quote #	Date of Quote	Version
26-3257Y	8/4/2026	1Y
Terms	FOB	Valid (days)
Net 30	Jobsite	30